

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

Name of Work: Construction of Drain from Gangamma Temple Road to Chikkasiddappa Layout
Amruthahalli in ward no 07 Byatarayanapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	107.9	KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3(I No-19.1, P No-143)	Cum	252.49	Rupees Two Hundred Fifty Two and Forty Nine Paise Only
2	74.7	KSRB2.8: Providing and Filling in foundation with granite/trap broken metal 100mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with all lead and lift complete as per specifications. specification. No. KBS (P.No.7, I.No.2.15 of PW,P&IWTD S.R 2016-17)	Cum	2574.74	Rupees Two Thousand Five Hundred Seventy Four and Seventy Four Paise Only
3	24.9	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No. 4.3 of PWD SR 2018-19)	Cum	5408.12	Rupees Five Thousand Four Hundred Eight and Twelve Paise Only
4	99.6	KSRB 4 6.1: Providing and removing centering, shuttering, strutting, propping etc., and removal off or mwork for foundations, footings, bases of columns for mass concrete including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(P.No.16, I.No.4.28 of PW, P&IWTD SR 2016-17)	Sqm	273.48	Rupees Two Hundred Seventy Three and Forty Eight Paise Only
5	498	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2(I No-4.31, P No-16)	Sqm	379.48	Rupees Three Hundred Seventy Nine and Forty Eight Paise Only
6	99.6	KSRB 4-6.3 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness above 200 mm including cost of all materials, labour complete as per Specification. Specification No. KBS 4.6.2(P.No.15, I.No.4.30 of PW,P&IWTD SR 2016-17)	Sqm	466.4	Rupees Four Hundred Sixty Six and Forty Paise Only
7	169.32	Providing and laying cement concrete using 20 mm. and down size granite coarse aggregates and fine aggregates of ready mixed concrete (RMC) M 20 for R.C.C works laid in 15 cms thick layers and well compacted vibrating, curing, for raft foundation column footing , main and secondary beams with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) P.No.18, I.No.4.48 of PW,P&IWTD SR 2018-19)	Cum	5770.64	Rupees Five Thousand Seven Hundred Seventy and Sixty Four Paise Only

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	14.39	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 (I No-4.46.2, P No-18)	Tonne	75223.96	Rupees Seventy Five Thousand Two Hundred Twenty Three and Ninety Six Paise Only

[Signature]

Executive Engineer

Byatarayanapura Division

BBMP, Bangalore - 92

Note:

- Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)
- Unit rates and prices shall be quoted by the Tender in Indian rupees.
- Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a))
- Where there is a discrepancy between the unit rate and the line item total resulting from multiplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))

" NTJ APPROVED "

[Signature]
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ